

June 08, 2009

Stadium Scoreboard and Sound System

ADDENDUM NO. 1

The following changes, additions, deletions or corrections shall become a part of the Contract Documents for the project named above and all other conditions shall remain the same. The bidders shall be responsible for transmitting this information to all affected subcontractors and suppliers prior to the closing of bids.

SPECIFICATIONS

Item No. 1: Reference Section 10416 Stadium Scoreboard and Sound System

A. Delete Section 1.02, Related Items

B. Revise Section 2.02, B, 3, to read as follows:

Maximum power requirement: 3,290 W @ 208VAC (single-phase).

C. Revise Section 2.02, E, 1, to read as follows:

Wireless Ethernet bridge

D. Insert Section **2.02, G, Electrical Power Supply, 1**, to read as follows:

Scope of work includes the following: Contractor shall provide, install and make final connections for all electrical from owner supplied electrical panel and breaker to scoreboard and sound system. Minimum wire requirements are 2 sets of #8 electrical wire and #10 ground wire. Wires are to be run in existing conduit between the press box (designated by owner) and the scoreboard location. Distance less than 600'. A licensed electrician must perform all high voltage electrical work.

E. Revise Section 2.07 to read as follows:

2.07 *AUDIO equipment*

A. *ADA hearing assist*

- 1. *Signal-to noise ratio: 80 dB***
- 2. *57 channels***
- 3. *Frequency response: 50Hz to 10kHz +/- 3dB***
- 4. *Receiver quantity: 20***

B. *Acceptable products:*

- 1. *Listen LS-03-216***
- 2. *Telex SMP400***

F. Delete in its entirety, Part 4, Leasing Option